

118
8

ANNEXURE -1' for Supply Installation Testing of DATA Logger

As per RDSO specification para -11, the information required to be furnished by purchaser are submitted herewith.

11.1.1 Total Number of Digital & Analog inputs to be monitored 512 digital & 32 Analog.

11.1.3 Whether RTU is required for monitoring of the equipments at distant place, No. of digital & analog inputs required in RTU: NIL.

11.2 Additional exceptional reports (other than those of mentioned in Para 6 of specification IRS S-99/2006) to be generated:

i). Point operation after arrival of train.

11.3 List of functions (in addition those mentioned in para 3.10) to be Monitored – Requirement will be as per Annexure-1 (a) - NIL.

11.4 a) Central Monitoring Unit (CMU) required. – No
b) FEP required: NO

- 1. Details of Analog Input
- 230 VAC – 06 no
- 110 VAC – 06 no
- 110 VDC – 02 no
- 60 VDC – 06 no
- 24 VDC – 08 no
- 40 VDC – 02 no
- 12 VDC – 02 no

N. S. 19/03/12
सहा. संचालक (सिग्नलिंग) महाराष्ट्र राज्य रेलवे, अ. ड. अ. वि. (सिग्नलिंग) (अ. ड. अ. वि.)

[Signature]
SSE महाराष्ट्र राज्य रेलवे, (सिग्नलिंग) अ. ड. अ. वि. (सिग्नलिंग) अ. ड. अ. वि. 58411