

(S) (M)

- a. Visual Inspection.
- b. Performance test

7.5 Visual Inspection

The Fuse Alarm System shall be visually inspected to ensure compliance with the relevant requirements specification of Railways.

7.6 Performance Test

Following test checks are to be conducted on each module of Fuse Alarm System to evaluate its performance.

- 1. When one main fuse blows / unscrewed, then buzzer should come along with main fuse failure indication.

8. Packing and labeling :

8.1 Units shall be packed in suitable boxes / crates, strong enough, with additional packing to prevent damage or loss to the unit during transit. Loose space inside the box/crate shall be filled up with suitable packing material.

Signature
16/1/13

(अनुसंधान) प्रमुख, जबलपुर
Divn. Sig. & Telecom Engineer
(Maint) W. C. Rly. Jabalpur

