

ELS/NKJ

Annexure

INDENT No. 6684-723 Dated 24/10/2013

Supply, Installation & commissioning of 0-3 V / 2000 Amp Digitally controlled DC high current Test set, as per specification: Input voltage - 230 V, AC 1 - Phase, 60 Hz, Out put: 0 - 2000 A @ 3.0 V DC.

Technical specification: -

Input Voltage	230 V, AC - 1-Phase, 60Hz
Output	0 - 2000 Amp @ 3.0 V DC
Indication	1) Mains ON 2) O/P ON 3) Trip
Meters	1) DC Ammeter 2) Digital Rectifier Controller- Protine 3) AC Voltmeter

208/16.11.13
ADEE/TRS/NKJ

[Signature]
16/11/13
Sr. DEE/TRS/NKJ

[Signature]
16.11.13
SSE/STORE
⊕ correction attested.
[Signature]
16/11/13
श्री. मण्डल विद्युत निरीक्षण अधिकारी (प. म. रेल.)
विद्युत लोको शेड, नई कान्हाजी जं. (प. म. रेल.)
Sr. Divisional Electrical Engineer (T.R.S.)
Electrical Loco Shed New Kani Jn. (W.C.R.)

O/C
[Signature]
16/11/13

West Central Railway

Annexure-II

To be submitted by the firm along with offer.

Tender specification as per Annexure-I	Specification quoted by the firm	Deviation if any with clarification

Signature of firm's