

ANNEXURE

Tender no 70.14.8009

49'x18'x11' Puff panel office cabin & partition at site " DUBRIKALAN STATION"

PUFF CABINE Sandwhich panels 80mm thick, having cladding of 0.4mm pre painted G.I sheet on both side, having tongue and groove section with cam locks for joints of panels for wall and ceiling . 4nos Door for room, 900mmx2000mm H opening , with aluminium frame lock, hinges & gasket. 8 nos ventilator made of G.I sheet 400mm x 600mm Secondary roof sheet hi-rib profiled made out of 0.4mm PPGL. Size 6x16m, with G.I chanals for slope.



SMM/G&C

अनूप सिंह यादव

Anoop Singh Yadav

वरि. सामग्री प्रबंधक/विडी

Sr. Materials Manager/S

पश्चिम मध्य रेल/जयलपुर

West Central Railway JBP.