

List of Approved NS Items

Sr. No.	Item No	Description of Item	Date of issue
01	L. NO. W-HQ / P&D / USSOR / NS Items.		25/10/2017
02	WCR/HQ/NS 0001	Inserting in to existing running track heavy and wide base PSC sleeper for BG track (Avg. weight 370 - 375 Kg) at all location in cutting / embankment, collected from cess / formation / toe of embankment, lying all along the track with necessary lead and lifts, including inserting standard fittings complete in all respect to specified gauge and perfect alignment with contractor's labour, tools & plants, including one round of packing and dressing of ballast as directed by engineer in charge.	02/04/2018
03	WCR/HQ/NS 0001/02	Supply of suitable manpower (in prescribed uniform) fit for Daily inspection of track and patrolling of track to the prescribed standard as per IRPWM/LWR Manual or as directed by engineer in charge (during day/night time ,as per requirement) for assisting Railway's patrolmen for safe and satisfactory running of trains. The rate includes cost of one Man per day, including ESI, EPF, and all taxes like GST etc., complete in all respect. Rate of item also includes provision of Uniform/safety tools & plants, safety equipments, consumables etc.	24/04/2018
04	WCR/HQ/NS 0005/01	Providing & Fixing of conference table to seat 22 person multiple seater as per lay out – top thickness 31.6 (18 mm + 12mm + 0.6mm DL (both sides) + 0.4mm membrane) Edge profile waterfall Edge 10mm radius on top edge and 5mm at bottom. Under structure made from 25mm PPB having a straight profile with half round edges and clad with 0.6mm thick post forming laminate.....	24/05/2018
05	WCR/HQ/NS 0005/02	Carrying out day to day maintenance job in the railway quarters / Service buildings in jurisdictions of SSE (W)'s / SSE (P-Way)'s of JBP/BPL/Kota division section by engaging semi – skilled worker for repair such as paints, glass panes, sanitary and water supply pipes/fitting/ other materials etc.....	30/07/2018
06	WCR/HQ/NS 0005/03	Supplying helper, khalasi/unskilled labour for assisting in various maintenance works to artisans for plumbing /Carpentry work/ smithy work/Masonry work/ painting / valve man/cleaner and gardener etc.....	30/07/2018
07	WCR/HQ/NS 0008/01	Installing and Commissioning of Handicapped / Divyang – friendly Modular Toilet unit of size 4'0" x 6'0" (approx.) with required foundation arrangement and cemented ramp suitable for wheel chair movement with S/S handrail fixed at suitable height on ramp and partition walls....	01/10/2018
08	WCR/HQ/NS 0010/01	Fabrication, manufacturing & supplying of pretention pre-stressed Hollow core concrete slab of (hollow area 11 to 25%) of different thickness & modular width 600 mm (or higher size) in controlled environment in factory premise with approved methodology, all requiste plant & machineries etc.....	26/10/2018
09	WCR/HQ/NS 0010/02	Providing & laying in position pre – stressing; HTS –steel strands (low relaxation confirming to IS – 6003) on hollow core bed by using mechanical pulling arrangement like Rabbit/ Bed master including all accessories for stressing & de – stressing operations as per approved make conforming to procedure as stipulated in IS 1343 (latest) & Grade FY – 1860 etc.....	26/10/2018
10	WCR/HQ/NS 0010/03	Erection & installation in proper position, Precast / Pre – stressed concrete elements / panels of different sizes in correct & final position with proper alignment / Line level and plumb at work site including all necessary arrangements for lifting placing & Alignment of elements,.....	26/10/2018
11	WCR/HQ/NS 0010/04	Providing non – shrink grout in suitable packing (water proof / moisture resistant) & Grouting of dowel tubes / Shear keys / joints of precast members with M-60 grade cementitious grout (Non shrink – Type) of approved make (fosroc / sika/ IS approved make) by suitable means (free flowing / pressure – pump),....	26/10/2018
12	WCR/HQ/NS 0010/05	Transportation of precast Elements by flat bed Trailor (Double / triple azle, with minimum 40 ft length with proper accessories like A frame ect.....	26/10/2018